



23 May 2023

Burns and Wilcox Center
First Floor Renovations
Tenant C

Addendum 2

The following addendum supersedes previous information and does hereby become part of the contract documents:

- Electrical: Panel C is a surface mounted 200 amp panel located in a storage room on the 2nd floor. It is located on the 2nd floor just left of the center column in the future tenant spaces, AA and BB, in the front of the building. Panel C is currently served from the old panel MDP in the 1st floor space. The contractor shall provide an additional 200 amp breaker in the new panel MDP, replacing the old panel MDP, to serve panel C. It does not have to be re-fed to panel MDP-2. Intercept the circuit and extend to the new MDP location.
- Provide Schluter strips on all exposed edges of Wall tile and Base tile in Mens and Women's toilet
- Form of Proposal: At bottom of page 1 of the Form of Proposal, strike through 2022 and write in 2023
- HVAC: There currently is an existing rooftop curb that can be used for the new unit to be added on the roof. Contractor shall be responsible for all Unistrut and mounting devices as well as pitch pocket penetration and membrane repair associated with the unit installation.

End of Addendum 2