



14 February, 2024

Columbus County
Building B HVAC Repairs

Addendum 1

The following addendum supersedes previous information and does hereby become part of the contract documents:

- Testing and balance (T.A.B.) shall be performed at all new and existing to remain V.A.V. boxes to design airflow valves as well as record airflow (CFM) at all diffusers. Contractors shall return after 90 days after completion to re-balance for occupant comfort per airflows directed by Project Engineer.

End of Addendum 1